

DEC 2 1996

COMMISSION

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 7/12/96 ⁷⁰⁸ LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42</u> N R <u>15</u> W	<u>J-13</u> ✓
	T <u>41</u> N R <u>15</u> W	<u>J-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Received & Filed this 8th day of
October 1996 at 11:34 A M

Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Thomas P. O'Brien, in a field survey on August 13, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13 (South 1/4 Corner Sec. 35)
Aug. 6, 1845 John Burt D.S. set gr. section post.
Y. Birch 8 N73W 19 do 7 N2½E 15

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 Nov. 28, 1979 Thomas P.O'Brien, RLS set Schoolcraft County Monument on "Township line by proportionate measure."

Dec. 29, 1993 Thomas P.O'Brien, PS recovered Schoolcraft Co. Mon. as set by Thomas P.O'Brien.

SURVEY & MONUMENTATION

DEC 1 8 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 Found Schoolcraft County Monument stamped to identify.

- Witnesses:
- 6" Maple - N32°W - 146.25'
 - 5" Maple - N4°W - 90.71'
 - 5" Maple - N27°E - 59.22'
 - Fd.8" Birch - N25°W - 54.20' Dead
 - Fd.8" Birch - N30°E - 63.50' Dead
 - Set4" Cedar Post - S4°W - 15.0'



Signed by Thomas P. O'Brien Date August 13, 1996
 Surveyor's Michigan License No. 21274