

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

SURVEY &  
RECORD DOCUMENTATION

MAY 18 1997

COMMISSION

DATE 12/10/96

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Schoolcraft</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T42NR15W	K-10
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Received & Filed this 30 day of  
Dec 1996 at 9:25 A M

Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Thomas P. O'Brien in a field survey on Dec. 17, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26	X	25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-10 Sept. 12, 1850 - Algernon Merryweather D.S. set gr. section post.  
Cedar 12 in. N45W 12 links Balsam 9 in. S75E 21 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 Dec. 17, 1996 - Thomas P. O'Brien, P.S. re-established corner by single proportionate measurement in centerline of county road. No evidence of G.L.O. survey or subsequent restoration recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 Set I.B. with cap # 21274 in monument box.

Witnesses : Power pole - N33°E - 65.57'  
Power pole - S 3° E - 249.34'  
6" Cedar - S22°W - 110.25'  
10" Tamarack - N51°W - 137.75'  
4" Cedar post - East - 33.0'



*Thomas P. O'Brien*

Signed by Thomas P. O'Brien

Date Dec. 26, 1996

Surveyor's Michigan License No. 21274