

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

DATE 12/10/96

Received & Filed this 30 day of  
Dec. 1996 at 9:21 A M

Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42</u> N R <u>15</u> W	L-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SURVEY &  
REMONUMENTATION

MAY 16 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													X
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas P. O'Brien in a field survey on Dec. 11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9 Sept. 10, 1850 - Algernon Merryweather D.S. set qr. section post.  
Beech 10 in. N65W 12 links Birch 8 in. S57E 25 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 Dec. 11, 1996 - Thomas P. O'Brien P.S. found 2" pipe at fence line intersection N,S,&W. Pipe has been used for corner position in previous surveys of record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 Schoolcraft County monument stamped to identify.

Witnesses: 10" Maple - N26°W - 36.68'  
4" Maple - N47°E - 22.15'  
6" Balsam - S12°E - 8.00'  
10" Maple - S74°W - 5.37'  
4" Cedar post - North - 1.0'



Signed by Thomas P. O'Brien  
Surveyor's Michigan License No. 21274

Date Dec. 26, 1996