

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

Received & Filed this 30 day of
Dec 1996 at 9:20 AM

Sigrid I. Hedberg
 Schoolcraft Co. Reg. of Deeds

DATE 12/10/96 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42NR15W</u>	<u>L-11</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

**SURVEY &
 REMONUMENTATION**

MAY 16 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Thomas P. O'Brien in a field survey on Dec. 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11												X	
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-11 Sept. 9, 1850 - Algernon Merryweather D.S. set qr. section post.
 Cedar 6 in. N80E 6.31 links Tamarack 7 in. S84E 6.43 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 Dec. 20, 1996 - Thomas P. O'Brien, P.S. re-established corner by single proportionate measurement. No evidence of G.L.O. survey or subsequent restoration recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Schoolcraft County monument stamped to identify.

Witnesses: 10" Cedar - N74°E - 376.45'
 4" Cedar - East - 488.53'
 12" Cedar - S84°E - 523.45'
 8" Ash - S75°E - 483.93'
 4" Cedar post - North - 2.0'



Thomas P. O'Brien

Signed by Thomas P. O'Brien
 Surveyor's Michigan License No. 21274

Date Dec. 26, 1996