

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

DATE 7/12/96

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Survey &
RECORDATION

NOV 2 1 1996

COMMISSION

For corners in

Schoolcraft
(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|-----------------------------|---------------|
| 1. Public Land Survey | T <u>42</u> N R <u>15</u> W | <u>L-13</u> ✓ |
| | T <u>41</u> N R <u>15</u> W | <u>L-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Received & Filed this 8 day of
October 19 96 at 11:25 A M
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Thomas P. O'Brien, in a field survey on August 13, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13 (South 1/4 Corner Sec. 36)
Aug. 6, 1845 John Burt D.S. set qr. section post.
Hemlock 12 S71E 14 Cedar 14 N65W 29

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 August 13, 1996 Thomas P. O'Brien P.S. Re-established corner by single proportionate measurement between K-13 and M-13.

Survey &
RECORDATION

DEC 1 6 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 Set Schoolcraft County Monument stamped to identify.

Witnesses: 4" Cedar - N27°W - 13.0'
4" Cedar - N28°E - 24.70'
4" Tamarack - N86°E - 37.67'
8" Cedar - N75°W - 26.40'
4" Cedar Post - S4°W - 1.0'



Signed by Thomas P. O'Brien Date August 13, 1996

Surveyor's Michigan License No. 21274

LIBER 4 PAGE: 42