

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

SURVEY &
 REMONUMENTATION

NOV 21 1996

DATE 9/13/96 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T. 42 R. 15W T. 42 R. 14W	M-2 A-2
2. Property Controlling in Section	S. T. R.	
3. Miscellaneous Property in Sec.	S. T. R.	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Received & Filed this 30 day of
Oct 19 96 at 11:32 A M
 Sigrid I. Hedberg
 Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

I, Thomas P.O'Brien in a field survey on Oct. 15, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	*
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-2 (East 1/4 corner, Sec.1, T42N-R15W)
 Sept.11, 1850 Algernon Merryweather, D.S. set Qr. section post
 Tamarack 5 in. S50W 80 links do 4 in. N70W 62"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2 Oct.15, 1996 Thomas P.O'Brien, P.S. set a Schoolcraft County monument
 at at proportionate distance and on line between the Township corner to the
 North and the Section corner to the South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 Set Schoolcraft County monument stamped to identify.

Witnesses:

- 8" Spruce N22°W 24.21' NBT
- 8" Jack Pine N28°E 21.59' NBT
- 8" Spruce N88°E 7.41' NBT
- 8" Jack Pine S48°W 87.43' NBT
- 4" Cedar Post North 2.0'

Thomas P.O'Brien

Signed by Thomas P.O'Brien
 Surveyor's Michigan License No. 21274

Date October 29, 1996

