

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

**LAND CORNER RECORDATION CERTIFICATE**

DATE Dec. 7, 1995

Filing Requirement of Act 74, Mich. P.A. 1970

JAN 8 0 1996

COMMISSION

Schoolcraft  
(County)

Located In:

Corner Code #

- |                                    |                         |              |
|------------------------------------|-------------------------|--------------|
| 1. Public Land Survey              | T 42 N R 15 W           | M-9 ✓<br>A-9 |
|                                    | T 42 N R 14 W           |              |
|                                    | T _____ R _____         |              |
|                                    | T _____ R _____         |              |
|                                    | T _____ R _____         |              |
| 2. Property Controlling in Section | S _____ T _____ R _____ |              |
|                                    | S _____ T _____ R _____ |              |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ |              |
|                                    | S _____ T _____ R _____ |              |

Received & Filed this 26 day of Dec. 1995 at 2:37 PM  
Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Thomas P. O'Brien, in a field survey on DEC. 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:


- M-9 (S.E. Corner Sec. 24)  
Sept. 10, 1850 Algernon Merryweather D.S. set corner post.  
Sugar 20 in. N2W 37 links do 10 " S80W 41 "  
  
April 18/51 Algernon Merryweather D.S. Corner 19&30 West Boundary.  
Beech 14 in. N67E 28 links Sugar 14 " S30E 47 "

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-9 Dec. 27, 1993 Thomas P. O'Brien, PS recovered 1/2" iron bar with plastic PS cap #28406. Testimony of William F. Bowman and measured distances verify corner was set by single proportionment measurement between M7 and M12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M9 Iron bar w|28406 cap set in monument box.  
Witnesses:  
8" Cedar S84°W 67.20'  
Power Pole N11°W 179.11'  
30" Willow clump N70°E 76.86'  
Power Pole S25°E 60.40'  
Cedar Post West 49.50'  
Centerline county road West 15.20'



Signed by Thomas P. O'Brien Date Dec. 20, 1995

Surveyor's Michigan License No. 21274