

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 N.R. 16 W


Scheelcraft COUNTY

DESCRIPTION OF CORNER 1/4 corner for Sections 4 and 5

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 1/19/61 with Bill Wallace and Art Enger

WITNESSES TO CORNER... 1 1/4" W. Pine (1/4" NBT) S 60° W 304 Links



9" W. Pine (1/4" NBT) S 21° E 401 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one Norway Pine B.T. bearing N 14° W, 462 Links. B.T. is a dead stub 50' high in excellent condition. Found by Art Enger. Corner lies in open marsh.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler

REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 2/23/61