

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Schoolcraft COUNTY
T $\frac{43}{42}$ N R 16 W

DESCRIPTION OF CORNER Section corner for sections $\frac{35}{2}$ / $\frac{36}{1}$ T43N R16W
T42N R16W

CORNER MONUMENT 1/2" x 12" reinforcing bar buried in G. M-94

DATE MONUMENT PLACED AND WITNESSED 7/22/69, F. J. Bray and M. Burnis

WITNESSES TO CORNER..... 17" R. Pine (NBT) S 42° E, 89 links



24" W. Pine (NBT) S 52° W, 123 links

16" R. Pine (NBT) N 42° E, 138 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed on line and the single proportioned measurement between the town corner one mile to the east and 1/4 corner 1/2 mile to the west.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/15/69
REGISTERED LAND SURVEYOR
Frank J. Bray

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68