

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970  
SCHOOLCRAFT CO. 3 CORNERS

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	T. <u>42</u> N. <del>XX</del> R. <u>16</u> W. <del>XX</del>	L-9, L-7	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION	<u>24</u> T. <u>42</u> N. <del>XX</del> R. <u>16</u> W. <del>XX</del>	5	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ R. _____ E. _____ S. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-8-8 10-15, 1987, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-9 1/4 Corner between Sections 24 & 25. OBT'S: Spruce 6, N43°E, 10 lks. & Ced. 12, North 9 lks
- L-7 North 1/4 Corner of Section 24. OBT'S: Spruce 8, N25°W, 35 lks. & Spruce 6, S16°E, 19 lks.
- 5 North 1/16 Corner of Section 24. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-9 Corner set midpoint on line between S.W. Section Corner and S.E. Section Corner of Section 24. Distance to stream East fits original call.
- L-7 Corner set at found squared and scribed post. Post matches a Carl Christenson post set at the N.E. Corner of Section 24 where he found original BT'S.
- 5 Corner set midpoint on line between North 1/4 Corner and Center of Section 24.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR Monument set at all three corners.

- |                                    |                             |                              |
|------------------------------------|-----------------------------|------------------------------|
| L-9 6" Dead Tam., N33°W, 42.3'     | L-7 3" Spruce, N68°E, 13.0' | 5 10" W. Birch, N20°E, 24.8' |
| SQ. Post, S45°W, 1.0'              | 3" Spruce, S84°E, 34.0'     | 5" W. Birch, South, 19.1'    |
| Sec. Cor., West, 2659.13'          | 4" Spruce, S25°E, 21.0'     | 6" Balsam, S71°W, 5.8'       |
| Sec. Cor., East, 2659.13'          | 3" Spruce, S17°W, 51.6'     | 10" W. Birch, West, 22.8'    |
| Center line of Grade, East, 115.0' |                             |                              |

SIGNED BY Gerald L. Wiggins DATE 2-11-88

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET