

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

SCHOOLCRAFT CO.-

3 CORNERS.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 ^{XX} S., R. 16 ^{XX} W.	K-7
2. PROPERTY CONTROLLING IN SECTION	24 T. 42 ^{XX} S., R. 16 ^{XX} W.	1 & 2
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-28 & 10-8, 19 87, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19 _____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-7 N.W. Section Corner of Section 24. *OBJ'S: Tamarack 6, S77°W, 10 lks. & Willow 6, S49°E, 8 lks*
- 1 West 1/16 Corner on North side of Section 24. *Not previously set.*
 - 2 East 1/16 Corner on North side of Section 24. *Not previously set.*

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-7 Corner set at found squared stake. *Distance South to rock ledge fits original. Also is in alignment with 3/4 mile of fence to South.*
- 1 Corner set midpoint on line between N.W. Corner and North 1/4 Corner of Section 24.
 - 2 Corner set midpoint on line between N.E. Corner and North 1/4 Corner of Section 24.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR Monument set at all three corners.

- K-7 10" W. Birch, S48°E, 11.1' 1 9" Tamarack, S24°E, 21.0' 2 10" Spruce, N23°W, 24.2'
 5" Cedar, S32°W, 14.2' 5" Cedar, S47°W, 12.65' 10" Spruce, N58°E, 4.5'
 8" Cedar, N55°W, 17.5' 8" Cedar, N29°W, 10.8' 6" Spruce, N45°E, 9.1'
 6" Cedar, N36°E, 8.4' 7" Cedar, S70°E, 6.9' 6" Spruce, S23°W, 4.1'

SIGNED BY

Gerald L. Wiggins
 Gerald L. Wiggins

DATE 2-12-88

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____

CHIEF OF SURVEY PARTY


DATE _____

APPROVED AND SIGNED BY _____

MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
 REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET