

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

SCHOOLCRAFT CO.

2 CORNERS

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> <sup>N.</sup> <del>X</del> R. <u>16</u> <sup>W.</sup> <del>X</del>	<u>H-12, L-11</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3-14 & 3-15, 1988, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

H-12 East 1/4 Corner of Section 36. OBTS: W. Birch 5, N86°W, 21 lks. 6 W. Birch 5, S44°W, 27 lks

L-11 Witness Corner to North 1/4 Corner of Section 36. (1/4 Corner lies 55.0' West in Bayou.)  
OBTS: Cedar 8, East 60 lks. 6 Cedar 10, S75°E, 75 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H-12 Corner set midpoint on line between N.E. Corner and S.E. Corner of Section

L-11 1/4 Corner computed by single proportionate measure. Set witness corner 55.0' East.  
1/4 Corner falls in Bayou which fits original measurement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
DNR Monuments placed at both corners.

H-12 8" Cedar, S86°W, 21.3'  
5" Cedar, N53°W, 28.9'  
6" Cedar, N18°W, 9.2'  
4" Cedar, S45°E, 18.1'

L-11 5" Cedar, S50°E, 3.9'  
5" Cedar, N81°W, 6.0'  
5" Cedar, N32°W, 7.2'  
4" Cedar, North, 19.6'

SIGNED BY Gerald L. Wiggins  
Gerald L. Wiggins

DATE 5-16-88

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_



FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET