

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

DATE 10/15/97

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

JAN 21 1998

SECTION

For corners in

Schoolcraft
(County)

Located in:

Corner Code #

1. Public Land Survey		T42NR16W	G-8
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Received & Filed this 9 day of
Dec 1997 at 3:47 P M
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Thomas P. O'Brien, in a field survey on Nov. 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21	X	22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-8 E 1/4 Corner Section 21
Aug. 14, 1850 - Algernon Merryweather D.S. set qr. section post.
Cedar 10 in. N49W 19 lks. Cedar 10 in. S15E 15 lks.
July 11, 1902 - Eugene Ford set post corner as noted in County Surveyors Record page 26 - 27.
Oct. 26, 1978 - Thomas P. O'Brien P.S. " Set on section line at GLO dist. South of Section Corner." LCRC recorded Liber 1, page 205.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 Nov. 6, 1997 - Thomas P. O'Brien P.S. recovered a 1/2" iron pipe with cap # 21274. Witnesses verify corner location. Reset iron pipe with Schoolcraft County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 Schoolcraft County Monument stamped to identify.

Witnesses: (Fd) 10" Cedar - S71°E - 42.0'
(Fd) 12" Cedar - S31°W - 31.20'
NBT 8" Cedar - N53°E - 61.70'
NBT 10" Cedar - S79°W - 40.62'
4" Cedar Post - North - 2.0'



Thomas P. O'Brien

Signed by Thomas P. O'Brien P.S.
Surveyor's Michigan License No. 21274

Date November 28, 1997

LIBER 4 PAGE: 128