

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

SURVEY &
REMONUMENTATION

DATE 10/15/97

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 21 1998

For corners in

| <u>Schoolcraft</u> (County) | Located in: | Corner Code # |
|---------------------------------------|--------------|---------------|
| 1. Public Land Survey | T42NR16W | H-9 |
| | T___R___ | _____ |
| | T___R___ | _____ |
| | T___R___ | _____ |
| 2. Property Controlling in Section | S___T___R___ | _____ |
| | S___T___R___ | _____ |
| 3. Miscellaneous Property in Sec. | S___T___R___ | _____ |
| | S___T___R___ | _____ |

SECTION
Received & Filed this 9 day of
Dec. 1997 at 3:42 PM
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on Nov. 4, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

H-9 S 1/4 Corner Section 22
Aug. 13, 1850 - Algernon Merryweather D.S. set qr. section post.
Beech 10 in. S40E 14 lks. do 4 in. N56W 23 lks.
Feb. 7, 1977 - Beryl M. Jones R.L.S. fd. 1" pipe. LCRC recorded Liber 1, page 236.
May 24, 1982 - Thomas P. O'Brien P.S. recovered subject corner and set iron bar w/21274 cap 50.0' South of and on the N + S 1/4 line of Section 27. LCRC recorded Liber 1, page 274.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9 Nov. 4, 1997 - Thomas P. O'Brien P.S. recovered spike in black top 50.0' North of above mentioned iron. Corner area has been filled in road improvement. Found Birch N40°E 58.40' (Cut) and I.B. verify corner position. Replaced spike with I.B. and O'Brien cap in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9 1/2" Iron bar with O'Brien cap #21274 in monument box.

Witnesses: (Fd.) 10" Birch - N40°E - 58.40'
12" R. Pine - N26°W - 47.65'
6" Maple - N35°E - 54.16'
14" Maple - S60°E - 88.57'
8" Maple - S27°W - 61.75'
4" Cedar Post - South - 40.0'



Signed by Thomas P. O'Brien P.S.

Date November 28, 1997

Surveyor's Michigan License No. 21274

LIBER Y PAGE: 123