

SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED

SURVEY &  
REMONUMENTATION

JAN 21 1998

DATE 10/15/97

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION \_\_\_\_\_

For corners in

Schoolcraft (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>16W</u>	<u>I9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received & Filed this 9 day of  
Dec. 1997 at 3:58 PM  
Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien, in a field survey on Nov. 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9								X					
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
I9 NW corner Section 26

Aug 13, 1850 Algernon Merryweather, DS set corner post  
Sugar 18 in N38E 15 lks Sugar 18 in S57W 7 lks.

July 11, 1902 Eugene Ford, County Surveyor "Ax buried to corner" as noted in County Surveyors Record of Survey page 27 and 27.

Feb. 7, 1977 Beryl M. Jones, RLS found 1/2" iron.  
LCRC recorded Liber 1, Page 236.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I9 Nov. 6, 1997 Thomas P.O'Brien, PS recovered 1/2" iron bar at E,W,S road intersection.  
Found witnesses verify corner location as found by Beryl M. Jones, RSL Feb. 7, 1997.  
Reset iron bar with 1/2" iron bar and OBRIEN 21274 cap in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
I9 1/2" iron bar with OBRIEN 21274 cap in monument box.

Witnesses:

- (FD) 10" Maple N40°E 58.0'
- (FD) Power Pole N45°W 40.95'
- NBT 18" Maple N43°E 118.52'
- NBT 6" Maple S46°E 83.78'
- NBT 26" Maple S39°W 119.89'
- NBT 20" Maple N37°W 121.70'

*Thomas P. O'Brien*

Signed by Thomas P.O'Brien, PS  
Surveyor's Michigan License No. 21274

Date Dec. 9, 1997

