

SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED

DATE 11/12/97

SURVEY &  
REMONUMENTATION

JAN 21 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

Schoolcraft Located In: Corner Code #  
(County)

- 1. Public Land Survey T42NR16W J-1  
T43NR16W J-13  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

Received & Filed this 9 day of  
Dec. 1997 at 3:55 P.M.  
Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Thomas P. O'Brien, in a field survey on Nov. 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-1 N 1/4 Corner Section 2  
June 3, 1841 - William A Burt D.S. set qr. section post.  
Cedar 6 N70E 22 do 12 N62W 13

August 9, 1967 - Frank J. Bray R.L.S. placed corner "at old wood post with point of older post along side. Signature tree has Slater's name and is dated 9/3/31. Several trees with old blazes facing corner."  
LCRC recorded Liber 3, page 175.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 Nov. 24, 1997 - Thomas P. O'Brien P.S. recovered a 1" iron pipe with 4" aluminum cap as set by Frank J. Bray August 9, 1967. Witnesses found verify corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 1" iron pipe with 4" aluminum DNR cap stamped to identify.

Witnesses : (Fd.) 7" Cedar - S41°E - 21½ lks.  
(Fd.) 9" Cedar - S43°W - 14 "  
(Fd.) 12" Cedar - N79°E - 9.48'  
NBT. 8" Cedar - N31°W - 34.50'  
Carsonite Post - North - 1.0'



Signed by Thomas P. O'Brien P.S.  
Surveyor's Michigan License No. 21274

Date November 25, 1997