

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

DATE 10/15/97

**SURVEY &
REMONUMENTATION**

JAN 21 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T42NR16W	J-11
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SECTION

Received & Filed this 23 day of
Dec. 1997 at 3:04 PM
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Thomas P. O'Brien, in a field survey on Oct. 31, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11										X			
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-11 N 1/4 Corner Section 35
Aug. 13, 1850 - Algernon Merryweather D.S. set qr. section post.
Birch 14 in. N49E 8 lks. do. 12 in. S24W 18 lks.

Sept. 19, 1985 - Neil E. Hill R.L.S. found iron with cap # 11368
in E + W fence line. LCRC recorded Liber 2, page 201.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11 Oct. 31, 1997 - Thomas P. O'Brien P.S. found iron pipe with cap #11368.
Witnesses found verify corner locaiton. Replaced pipe with Schoolcraft
County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11 Schoolcraft County Monument stamped to identify.
Witnesses: (Fd.) 7" Spruce - N30°W - 24.94'
(Fd.) 21" Willow - N10°W - 28.85'
(Fd.) Fence Post - S85°E - 5.72'
(Fd.) Fence Post - S25°W - 1.58'
4" Cedar Post - North -1.0'



Thomas P. O'Brien

Signed by Thomas P. O'Brien P.S.

Date November 28, 1997

Surveyor's Michigan License No. 21274

LIBER 4 PAGE: 150