

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

**SURVEY &
REMONUMENTATION**

DATE 10/15/97 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 21 1998

For corners in

Schoolcraft _____ Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 2N R 16W K-7
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

SECTION

Received & Filed this 9 day of Dec. 1997 at 4:02 P M
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Thomas P. O'Brien, in a field survey on Nov. 7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		19		17		16		15		14		13	
7											X		
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-7 NW Corner Section 24
Aug. 12, 1850 - Algernon Merryweather D.S. set corner post.
Tamarack 6 S77W 10 lks. Willow 6 S49E 8 lks.

Sept. 28, 1987 - Gerald L. Wiggins L.S. set corner " at found squared stake. Distance South to rock ledge fits original. Also is in alignment with 3/4 mile of fence to South." LCRC recorded Liber 2, page 115.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7 Nov. 7, 1997 - Thomas P. O'Brien P.S. recovered a 1" iron pipe with 4" aluminum cap as set by Gerald L. Wiggins September 28, 1987.
Witnesses found verify corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7 1" iron pipe with 4" aluminum DNR cap stamped to identify.

Witnesses: (Fd.) 10" W. Birch - S48°E - 11.10'
(Fd.) 5" Cedar - S32°W - 14.20'
(Fd.) 8" Cedar - N55°W - 17.50'
(Fd.) 6" Cedar - N36°E - 8.40'
4" Cedar Post- North - 1.0'



Signed by Thomas P. O'Brien P.S.
Surveyor's Michigan License No. 21274

Date November 26, 1997