

JAN 21 1998

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 10/15/97 LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft (County) Located In: Corner Code #
1. Public Land Survey T42NR16W K-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Received & Filed this 9 day of December 1997 at 3:41 PM Sigrid I. Hedberg Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Thomas P. O'Brien in a field survey on Nov. 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 and an 'X' at row 8, column J.

A. Description of original monument and accessories and/or subsequent restoration:

K-8 W 1/4 Corner Section 24
Aug. 12, 1850 - Algernon Merryweather D.S. set qr. section post.
Soft Maple - 7 in N89E 17 lks. Birch 18 in S85W 12 lks.
Sept. 1912 - Ernest Weaver, County Surveyor re-established this corner as noted on pages 44 & 45 of the Record of Surveys - Liber 1, form the original witness trees.
June 6, 1983 - William F. Bowman L.L.S. "set corner at the intersection of old road grade running to the West and a fence line North & South."
Corner position fits well with dimensions that Weaver notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

K-8 Nov. 5, 1997 - Thomas P. O'Brien P.S. recovered I.B. (bent) as set by William F. Bowman L.L.S. on June 6, 1983. Witnesses found verify corner position. Replaced I.B. with Schoolcraft County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 Schoolcraft County Monument stamped to identify.
Witnesses: (Fd.) 4" Birch - S60°W - 40.45'
(Fd.) 6" Maple - S35°W - 31.30'
(Fd.) 12" Twin Maple - N55°W - 38.80'
NBT. 8" Maple - N26°W - 76.56'
4" Cedar Post - South - 6.0'



Signed by Thomas P. O'Brien P.S. Date November 28, 1997
Surveyor's Michigan License No. 21274