

JAN 21 1998

SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED

DATE 10/15/97 <sup>0013</sup> LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42NR16W</u>	<u>K-9</u>
	T <u>    </u>	<u>    </u>
	T <u>    </u>	<u>    </u>
	T <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u>	<u>    </u>
	S <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u>	<u>    </u>
	S <u>    </u>	<u>    </u>

Received for Record 12-9 19 97 at 3:40  
P.M. Liber 4 of Land Corners  
page 121 Sigrid I. Hedberg,  
Register of Deeds.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien, in a field survey on Nov. 5, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9											X		
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-9 NW Corner Section 25  
Aug. 12, 1850 - Algernon Merryweather D.S set corner post.  
Cedar 12 in. N24W 15 lks. Cedar 10 in. S20E 11 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9 Nov. 5, 1997 Thomas P. O'Brien P.S. recovered a 3/8" iron rod with top bent, bottom of iron straight. Replaced iron rod with Schoolcraft County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 Schoolcraft County Monument stamped to identify.

Witnesses: 6" Cedar - N59°E - 70.61'  
8" Cedar - S32°E - 95.86'  
6" Cedar - S29°W - 75.38'  
Power Pole - N66°W - 62.38'  
4" Cedar Post - North - 25.0'



Signed by Thomas P. O'Brien  
Surveyor's Michigan License No. 21274

Date November 28, 1997

LIBER 4 PAGE: 121