

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

**SURVEY &
REMONUMENTATION**

JAN 21 1998

DATE 10/15/97 **LAND-CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>16W</u>	<u>K-10</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Received & Filed this 23 day of
Dec. 1997 at 3:00 PM
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P.O'Brien, in a field survey on Nov. 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-10 West 1/4 Corner, Section 15
Aug. 12, 1850 Algernon Merryweather, D.S. set qr. section post
Balsam 8 in S30E 13 lks. B. Ash 10 in N79W 24 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 Nov. 5, 1997 Thomas P.O'Brien, P.S. reestablished corner by single proportionate measurement between K9 and K11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 Schoolcraft County monument stamped to identify.
Witnesses:
36" Maple S23°W 120.88'
6" Cedar N80°E 79.60'
14" Hemlock N24°E 80.92'
Fence Corner S75°E 14.12'
Fence post S75°W 11.90'



Signed by Thomas P.O'Brien
Thomas P.O'Brien, P.S.
Surveyor's Michigan License No. 21274

Date Dec. 23, 1997