

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED
 DATE 11/12/97

SURVEY & REMONUMENTATION

JAN 21 1998

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft
 (County)

Located In:

Corner Code #

1. Public Land Survey

T42N R16W

L-1 ✓
L-13

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R
 S T R
 S T R

Received & Filed this 9 day of
Dec 1997 at 4:03 P M
 Sigrid I. Hedberg
 Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on Nov. 24, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-1 N½ Corner Section 1
 June 3, 1841- William A. Burt D.S. set qr. section post.
 Hemlock 8 N58E 20 W. Pine 18 N52W 2
 July 23, 1969 - Frank J. Bray R.L.S. set corner midway and on line between town corner to the East and section corner to the West.
 LCRC recorded Liber 3, page 173.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 Nov. 24, 1997 - Thomas P. O'Brien, P.S. recovered a 1" pipe w/ 4" aluminum cap stamped to identify as set by Frank J. Bray on 7/23/69. Witnesses found verify corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 1" iron pipe with 4" aluminum DNR cap, stamped to identify.

Witnesses: (Fd. cut stump) 9" R. Pine- N29°W - 22 lks.
 (Fd. cut stump) 7" R. Pine- East - 81.5 lks.
 NBT. 10" Oak - N43°W - 122.38'
 NBT. 10" Oak - N64°E - 123.85'
 NBT. 8" Oak - S77°E - 126.05'
 NBT. 12" Oak - S37°W - 97.36'
 Carsonite post- North - 1.0'



Signed by Thomas P. O'Brien P.S.
 Surveyor's Michigan License No. 21274

Date November 25, 1997