

SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED

DATE 11/12/97

SURVEY &  
REMONUMENTATION

JAN 21 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>16W</u>	<u>L-3</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Received & Filed this 23 day of  
Dec 1997 at 3:16 p M  
Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien, in a field survey on Dec. 4, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													X
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-3 North 1/4 Corner Section 12  
Aug. 10, 1850 - Algernon Merryweather D.S. set qr. section post.  
Cedar 9 in. N59E 9 links Do. 10 in. S58W 11 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 Dec. 4, 1997 - Thomas P. O'Brien P.S. reestablished corner by single proportionate measurement between K3 and M3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 Schoolcraft County Monument stamped to identify.

Witnesses: 8" Cedar - N12°E - 54.45'  
10" Cedar - S48°E - 67.70'  
12" Cedar - S16°E - 58.14'  
6" Cedar - N87°W - 67.75'  
4" Cedar Post - North - 2.0'



Signed by Thomas P. O'Brien P.S.  
Surveyor's Michigan License No. 21274

Date December 19, 1997

LIBER 4 PAGE: 162