

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

DATE 10/15/97

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

JAN 21 1998

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 16W T 41N R 16W T ___ R ___ T ___ R ___	L13 ✓ L1 _____ _____
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____

SECTION

Received & Filed this 9 day of
Dec 1997 at 4:00 P M
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P.O'Brien, in a field survey on Oct. 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	19		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													X

A. Description of original monument and accessories and/or subsequent restoration:

L13 S 1/2 corner Section 36
Aug. 4, 1845 John Burt, DS set qr. section post
Hemlock 14 N50E 13 Spruce 4 N3W 12

Sept. 16, 1912 Earnest Weaver, County Surveyor set cedar stake as noted in Record of Surveys pages 36 and 37.

June 19, 1978 Thomas P.O'Brien, PS found 1 1/2" iron pipe at corner location. LCRC recorded in Liber 1, page 182.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L13 Oct. 28, 1997 Thomas P.O'Brien, PS recovered 1 1/2" iron pipe. Found witnesses verify corner location. Replaced iron pipe with Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L13 Schoolcraft County monument stamped to identify.

Witnesses:

- (FD) 6" Cedar N25°E 46.65'
- (FD) 20" Red Pine S10°W 55.35'
- (FD) 8" Hemlock S65°W 79.70'
- NBT 12" White Pine S56°E 78.55'
- NBT 8" Hemlock S32°W 75.15'
- NBT 8" Hemlock S39°W 86.65'
- 4" Cedar Post East 10.0'

Signed by Thomas P.O'Brien, PS
Surveyor's Michigan License No. 21274

Date Dec. 9, 1997

