

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

**SURVEY &  
REMONUMENTATION**

**DATE 7/12/96** LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MAY 16 1997

For corners in

**COMMISSION**

Schoolcraft Located In: Corner Code #  
(County)

- 1. Public Land Survey T42NR15W A-11  
T42NR16W M-11 ✓  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

Received & Filed this 16 day of  
December 19 96 at 11:53 AM  
Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien in a field survey on Oct. 25, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	13			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

- A-11 (N.W. Corner Sec. 31)  
Aug. 3, 1845 John Burt D.S. set corner post.  
Cedar 20 N45W 36 do 14 S66W 4  
  
Sept. 20, 1850 Algernon Merryweather, D.S. Corner 30&31 West Boundary.  
Birch 10 in. N40E 15 lks. S. Maple 20" S70E 42"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-11 Feb. 20, 1957 - Billy D. Buckler, R.L.S. found 1" pipe with brass cap set by Carl Christensen from " Cedar B.T. bears S45W 4 links."  
  
Oct. 25, 1996 - Thomas P. O'Brien, P.S. recovered iron pipe with brass cap as set by Carl Christensen from an original bearing tree " Cedar 14" S66W 4 links" as noted in County Surveyors book. Original B.T. has been cut, stump is tipped, but still in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-11 1" pipe with 4" brass cap stamped to identify.  
Witnesses: Fd. 9" Cedar- S60°E- 66 lks.  
" 8" Cedar- S26°W- 48½ lks.  
" 10" Cedar- N60°W- 64 lks.  
NBT 10" Maple- N57°E- 61.38'  
OBT 14" Cedar Stump- S45°W - 4 lks.  
4" Cedar post - East - 1.0'



Signed by Thomas P. O'Brien  
Surveyor's Michigan License No. 21274

Date Nov. 18, 1996