

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SCHOOLCRAFT
(County)

Located In:

Corner Code #/

1. Public Land Survey	T	---	R	---	---
	T	---	R	---	---
	T	---	R	---	---
	T	---	R	---	---
2. Property Controlling In Section	S	35	T	42N R 17W	15
	S	35	T	42N R 17W	2
3. Miscellaneous Property in Sec.	S	35	T	42N R 17W	6
	S	35	T	42N R 17W	7

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, Gerald L. Wiggins, in a field survey on 11-8 & 11-21, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 15 West 1/16 Corner on South side of Section 35. Not previously set.
- 2 East 1/16 Corner on North side of Section 35. Not previously set.
- 6 Northeast 1/16 Corner of Section 35. Not previously set.
- 7 North 1/16 Corner on East side of Section 35. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 15 Corner set midpoint on line between S.W. Section Corner and South 1/4 Corner of Section 35.
- 2 Corner set midpoint on line between N.E. Corner and North 1/4 Corner of Section 35.
- 6 Corner set at center of N.E. 1/4 Section 35 by closed traverse.
- 7 Corner set midpoint on line between N.E. Corner and East 1/4 Corner of Section 35.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


- 15 DNR MONUMENT. 2 DNR MONUMENT 6 1" PIPE W/Plastic RLS CAP
- 6" Cedar, S35°E, 23.5' 8" Maple, N10°W, 21.3' 12" Y. Birch, S24°W, 34.3'
- 12" Cedar, S24°E, 22.95' 5" Maple, N74°W, 32.8' 5" Beech, S25°E, 65.8'
- 18" Birch, S65°W, 13.2' 7" Maple, S43°W, 52.8' 6" Cherry, N51°E, 41.95'
- 5" Balsam, N7°E, 7.2' 10" Maple, S10°W, 32.9' 8" Maple, N18°W, 46.65'
- 7 DNR MONUMENT 12" Beech, S10°E, 21.4' & 10" Beech, S28°W, 25.05' &
14" Beech, S71°W, 27.4' & 8" Beech, N85°W, 25.7'

Signed by

Gerald L. Wiggins

Date 4-2-90

Surveyor's Michigan License No. 23521



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, MAY 14, 1970
 REVISED JAN., 1983