

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SCHOOLCRAFT
(County)

Located In:

Corner Code #:

- | | | |
|------------------------------------|------------------|------|
| 1. Public Land Survey | T 42N R 17W | K-11 |
| | T 42N R 17W | K-10 |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S 26 T 42N R 17W | 7 |
| | S 26 T 42N R 17W | 14 |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, Gerald L. Wiggins, in a field survey on 9-25 & 10-10, 1989, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-11 S.E. Section Corner of Section 26. OBT'S: 16" Hemlock, N50°W, 35 lks. & 12" Hemlock, S20°E, 6 lks.
- K-10 East 1/14 Corner of Section 26. OBT'S: 10" Sugar, N50°W, 91 lks. & 8" Hemlock, S85°E, 20 lks.
- 7 North 1/16 Corner on East side of Section 26. Not previously set.
- 14 South 1/16 Corner on East side of Section 26. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-11 Corner replaced at found 1 1/2" pipe as set by Gregory A. Shanko L. S. #1934 in 1940.
- K-10 Corner replaced by single proportionate measure between N.E. Corner and S.E. Corner of Section 26 and from witness monument East as set by Gregory A. Shandko L.S. #1934 in 1940.
- 7 Corner replaced by single proportionate measure between N.E. Corner and S.E. Corner of Section 26 and from witness monument East as set by Gregory A. Shandko L.S. # 1934 in 1940.
- 14 Corner replaced by single proportionate measure between N.E. Corner and S.E. Corner of Section 26 and from witness monument East as set by Gregory A. Shanko L.S. #1934 in 1940.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-11 DNR MONUMENT K-10 1" Pipe W/Plastic RLS Cap
Center Line Road 25.6' East Bent over Witt. Mont. East 33.7'
7" Cedar, S43°W, 24.6' 14" W. Birch, N55°E, 31.6'
8" Cedar, N42°W, 29.9' 12" W. Birch, S58°W, 42.2'
10" Aspen, N89°E, 63.5' 12" Maple, S35°E, 59.4'
14" Aspen, N76°E, 69.2'
- 7 1" Pipe W/Plastic RLS Cap, Witt Mont., East, 32.8' & 10" Tamarack, N85°E, 65.35' & 10" S. Maple, N22°W, 45.0' & 8" S. Maple, S62°W, 56.2'.
- 14 1" Pipe W/Plastic RLS Cap, Witt. Mont., East, 33.18", 6" Cedar, N70°W, 78.35' & P. Pole, N47°W, 45.65' & 10" Cedar, S42°W, 105.2'.

Signed by Gerald L. Wiggins Date 4-2-90
Surveyor's Michigan License No. 23521

FORM APPROVED BY MICHIGAN STATE DEPARTMENT OF LAND SURVEY

