

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T...43 NR...14...W

...Schoolcraft...COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 11, 12, 14, and 13

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 12" Elm (S 11 NBT) .. N 51° W .. 61 Links

12" Yellow Birch (S 13 NBT) .. S 42° E .. 135 Links ..

11" Yellow Birch (S 12 NBT) .. N 83° E .. 82 Links ..

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED. This corner was replaced from one Elm B. T. bearing S 68° W 28
Links. Tree green and in excellent condition. Chopped out tree and found
scribe marks on face. Age of tree confirmed by annual growth ring count.
Corner found by Forestry Division Survey Crew.

Corner was placed and witnessed February 20, 1958.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR
Billy D. Buckler

DATE 2/25/60