

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 14 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 23, 24, 25, 26

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8/15/61

WITNESSES TO CORNER... 4" B. Spruce (S 23 NBT) N 32° W 10 1/2 Links



5" B. Spruce (S 26 NBT) S 35° W 31 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by proportioned distances to corners 1 mile to North and 2 miles to South.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 9/15/61
REGISTERED LAND SURVEYOR
Billy D. Buckler