

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 14 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 28, 29, 32, 33

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 5/4/61 with D. St. Ours

WITNESSES TO CORNER... 5" Cedar (S 29 NBT) N 13 deg. W 42 1/2 Links



5" Cedar (S 28 NBT) N 40 deg. E 37 Links

8" Cedar (S 33 NBT) S 56 deg. E 62 1/2 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced at old Iron Pipe set by unknown Surveyor. Found remains of Tamarack Stump bearing S 61 deg. W, 06 Links (probable B.T.) Position checks well with corners North, South and East. Placed location poster 13,00 chains North on Road.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 9/15/61
REGISTERED LAND SURVEYOR
Billy D. Buckler