

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 14 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Secs. 27/34

CORNER MONUMENT 1" x 4" Iron Pipe

DATE MONUMENT PLACED AND WITNESSED 3/10/64 by A.O. Enger, recorded and checked by
Bray and Hinds 5/26/65

WITNESSES TO CORNER..... 7" Red Pine (1/4S NBT), S 03° E, 46 1/2 Lks.



12" Red Pine (1/4S NBT) N 49° W, 68 Lks.

7" Jack Pine (1/4S NBT), N 52° E, 69 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was set by proportionate measurement on line between Section Corners as computed by Billy D. Buckler, D.L.S.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/8/1965
REGISTERED LAND SURVEYOR