

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

SURVEY &
REMONUMENTATION

FEB 08 2001

DATE 10/10/00 *TOB*

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft (County)	Located In:	Corner Code #	SIGRID HEDBERG SCHOOLCRAFT CO. REGISTER Page 1 of 1 JLV Date 12/19/2000	1P LC 4/382 Time 11:53:25
1. Public Land Survey	T <u>42</u> N R <u>14</u> W	H1		
	T <u>43</u> N R <u>14</u> W	H13 ✓		
	T ___ R ___	_____		
	T ___ R ___	_____		
2. Property Controlling in Section	S ___ T ___ R ___	_____		
	S ___ T ___ R ___	_____		
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____		
	S ___ T ___ R ___	_____		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 11/6/00, ~~19~~¹⁹X do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Oct. 20, 1850 Algernon Merryweather, DS set qr section post Cedar 12 N54W 49
Sugar 14 N10W 23

Dec. 28, 1961 Billy D. Buckler, RLS "Re-established by single proportionate measurement between Section Corner 1/2 mile West and 1/4 corner 2 miles east and in old E and W fence line.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 6, 2000 Thomas P. O'Brien, PS recovered Mich. Dept. of Cons. cap on pipe stamped to identify and verified by distances to corners East and West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Michigan Department of Conservation cap on pipe.

Witnesses:
24" Maple N58°E 88.63'
16" Maple S74°E 85.18'
6" Spruce S41°E 23.90'
3" Spruce S30°W 17.80'
Carsonite Post South 1.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec. 11, 2000