

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

DATE 10/10/00 *DOB*

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
LAND CORNER RECORDATION CERTIFICATE LC 4/363
Filing Requirement of Act 24 of 1970 P.A. 21970 Time 11:53:01

For corners in

Schoolcraft
(County)

Located in: Corner Code #

1. Public Land Survey T 42NR14W I1
T 43NR14W I13 ✓
T ___ R ___
T ___ R ___

2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/363
JLO Date 12/19/2000 Time 11:53:01

**SURVEY &
REMONUMENTATION**

FEB 08 2001

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____ SECTION _____

I, Thomas P. O'Brien, in a field survey on 10/9/00, ^{xx}19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Oct.20, 1850 Algernon Merryweather, DS section corner Sections 2,3 Tamarack 7 in S70W 10 links Spruce 6 in North 5 links Tamarack 14 N44E 19 do 10 N45W 23

Sept.15, 1961 Billy D. Buckler, RLS "This corner was re-established by single proportionate measurement between 1/7 corner 1/2 mile west and Section Corner 1 mile East. No original evidence.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct.9, 2000 Thomas P. O'Brien, PS found Mich. Dept. of Cons.cap on pipe as set by Buckler and verified by witnesses and distances to corners E and W. Accepted corner as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Michigan Department of Conservation cap on pipe.
Witnesses:
12" Cedar N59°E 24 links- existing Buckler BT.
10" Cedar S76°W 15 links- existing Buckler BT.
6" Cedar N41°W 19.40'
4" Cedar S56°E 23.15'
Carsonite Post North 1.0'



Thomas P. O'Brien

Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec. 12, 2000

LIBER 4 PAGE 363