

SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED

DATE 10/10/00 DOB

SURVEY &  
REMONUMENTATION

FEB 08 2001

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey

T 42N R14W

K1

T 43N R14W

K13 ✓

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

SIGRID HEDBERG

SCHOOLCRAFT CO. REGISTER

1P

Page 1 of 1

LC 4/372

JLO Date 12/19/2000

Time 11:53:19

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien, in a field survey on 11/10/00, ~~10x~~ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Oct. 20, 1850 Algernon Merryweather "set post common to Section 35 and 36 (T43N R14W) Aspen 10 N47E 11 W. Birch 12 N38W 20

April 7, 1851 Algernon Merryweather "corner 1 and 2 North boundary Cedar 12" S37W 58 links Birch 12 " S29E 50 "

Sept. 15, 1961 Billy D. Buckler, RLS "re-established by single proportionate measurement and in line between 1/4 corner 1/2 mile East and 1/4 corner 1 1/2 miles West."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov.10, 2000 Thomas P. O'Brien, PS recovered Michigan Dept. of Cons. cap on pipe stamped to identify and verified by distances East and West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Michigan Department of Conservation cap on pipe.

Witnesses:

10" Balsam S81°W 25.35'

4" Balsam N25°E 25.92'

12" W. Birch S25°E 24.20'

12" Maple S21°W 26.90'

Carsonite PPost North 1.0'



Signed by Thomas P. O'Brien

Surveyor's Michigan License No. 21274

Date Dec. 11, 2000

LIBER 4 PAGE: 37d