

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Schoolcraft	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 43N R 14W	E7
	T 43N R 14W	E9
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on E7 05/18/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(E7) Corner common to Sections 16-17-20-21. 1850 - Established by Algernon Merryweather Deputy Surveyor. Set post. W.Pine 20" N65W 18 links, Birch 7" S60E 14 links. 1959 - Remonumented in the original position by Billy D. Buckler RLS from W.Pine B.T. N65W 18 links, found with scribe marks plain, stump in poor condition. Set 1" ID I.pipe with 4" brass cap. 18" Red Pine N11W 87 links, 11" Jack Pine N65E 32 links, 7" Jack Pine S52W 62 links.

(E9) Corner common to Sections 20-21-28-29. 1850 - Established by Algernon Merryweather Deputy Surveyor. Original bearing trees: N.Pine 12" N80W 21 links, W.Pine 12" S35E 34 links. 1959 - Remonumented in the original position by Billy D. Buckler RLS from Yellow Pine B.T. N80W 21 links and remains of White Pine B.T. S35E 34 links. Found old stake on ground and several blazes in vicinity. Set 1" ID I.pipe with 4" brass cap. 9" Jack Pine N29W 13 links, 9" Jack Pine N41E 16 links, 7" Jack Pine S13W 26 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(E7) Found the 1959 monument in good condition and at record bearing and distance from the NBT Red Pine NW and the NBT Jack Pine SW, both in good condition. The NBT Jack Pine NE is gone. The stump of the OBT W.Pine N65W is now gone. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(E9) Found the 1959 monument in good condition and at record bearing and distance from two of the three 1959 witnesses. The NBT Jack Pines NW and NE are in place and in good condition. The Jack Pine SW is now gone. The stump remains of the original BTs are in place. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(E7) Fd. 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
 27" R.Pine N02E 58.35' mrkd "S16" 1959 NBT  
 12" J.Pine S46W 34.28' mrkd "S20" do  
 9" Balsam S89E 97.75' mrkd "S21 NBT"  
 5" Maple N72W 30.3' "S17 NBT"  
 Bearings are magnetic.

(E9) Fd. 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
 13" J.Pine N22W 9.02' 1959 NBT  
 14" J.Pine N45E 10.78' do  
 7" Spruce S40E 11.37' mrkd "S28 NBT"  
 7" Spruce S40W 7.82' "S29 NBT"  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 08/25/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

