

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD

~~Schoolcraft~~ COUNTY


T 44 & 43N R's 15 & 16W

DESCRIPTION OF CORNER Town corner for sections $\frac{T44N R16W}{T43N R16W}$ $\frac{36/31}{1/6}$ $\frac{T44N R15W}{T43N R15W}$

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/29/69, F. J. Bray with M. Burnis

WITNESSES TO CORNER..... 14" W. Pine (S.6) (NBT) S 68° E, 93½ links



18" R. Pine (S.1) (NBT) S 01° W, 111 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between section corners two miles to east and to west and three miles to the south and 1/4 corner 2½ miles to the north.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE 11/18/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68