

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

SCHOOLCRAFT COUNTY


T 43 N R 15 W

DESCRIPTION OF CORNER Section corner for Sections <sup>26/25</sup> 35/36

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 4/11/72 F. J. Bray with M. Burnis

WITNESSES TO CORNER..... 3" Tamarack (X) N65°W, 52.2'



2" Tamarack (X) N34°E, 37.9'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between the section corners one mile to the east and south, three miles to the north and two miles to the west. No original evidence was found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Frank J. Bray*  
REGISTERED LAND SURVEYOR  
Frank J. Bray

DATE

5-12-72

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68