

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

SCHOOLCRAFT COUNTY


T 43 N R 15 W

DESCRIPTION OF CORNER Section corner for Sections $\frac{3}{2}$
10/11

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 4/5/72 F. J. Bray with M. Burnis

WITNESSES TO CORNER..... 18" R. Pine (S. 10 NBT) S78°W, 15.0'



18" R. Pine (S. 3 NBT) N38°W, 23.1'

AND


CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between the section corners one mile to the north and east, two miles to the west and five miles to the south. No original evidence was found.

SURVEYOR'S SEAL

SIGNED


REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

5-12-72

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68