

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


SCHOOLCRAFT COUNTY
T 43 N R 15 W

DESCRIPTION OF CORNER Section corner for Sections ^{23/24}
26/25

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 4/11/72 F. J. Bray with M. Arnis

WITNESSES TO CORNER..... 12" J. Pine (S.24) (NBT) N89°E, 117.0'



12" J. Pine (S.24) (NBT) N30°E, 213.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between the section corners one mile to the east and south and two miles to the north and west. No original evidence was found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray DATE 5-12-72
REGISTERED LAND SURVEYOR
Frank J. Bray

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68