

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 15 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Sections 15/22

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 4/15/64 by A.O. Enger, Recorded and monumented  
5/18/1965 by Bray and Hinds.

WITNESSES TO CORNER..... 13" W. Pine. (1/4S NBT), N 79° E, 46 1/2 Lks.



CIRCLE CORNER REGISTERED

6" W. Pine (1/4S NBT), N17° W, 40 Lks.

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was found by W. J. Wallace, set from 2 Original BT's now stumps.  
W. Pine 28", S 35° E, 26 Lks. and W. Pine 26", N 80° W, 29 Lks. BT to NW has  
lower blaze with axe notch, possible traces of scribe marks. BT to SE has no  
marks, but agrees in bearing and distance from corner.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/8/1965  
REGISTERED LAND SURVEYOR