

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 15 & 16 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner for Secs 25-36 T43N R 16W and 30-31 T43N R 15W

CORNER MONUMENT 1" x 6" Iron Pipe

DATE MONUMENT PLACED AND WITNESSED 7/15/63 by A.O. Enger, 5/13/65 checked and recorded by Bray and Hinds.

WITNESSES TO CORNER.....5" Y. Pine (S30 NBT), N 37° E, 145 lks.



CIRCLE CORNER REGISTERED

10" Y. Pine (S25A NBT), N 17° W, 188 lks.

5" Y. Pine (S25B NBT), N 74° W, 190 lks.

AND

2" Iron Pipe with Brass Cap N 3½° W, 187 lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from two original BTs found by A.O. Enger. Spruce Pine 10, S 50° E, 58 lks, Spruce Pine 12, N 63° E, 51 lks. C. Christonson has witness corner 2" Iron pipe with Brass Cap Marked ~~25~~ 30 10 rods south, which is in error  
36 31

as he possibly took the BT to the SE for the BT to the NE to set the Section Corner A 2" Rusted pipe is down and lies in the Lake approximately 10 rods South of his witness corner.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/8/1965  
REGISTERED LAND SURVEYOR