

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 15 W

Schoolcraft COUNTY


DESCRIPTION OF CORNER Section Corner for Secs. 21-22-27-28

CORNER MONUMENT 2" Iron Pipe with 2 1/2" Brass Cap set by Carl Christensen

Checked and recorded 5/18/65

DATE MONUMENT PLACED AND WITNESSED 6/19/64 by A.O. Enger, Bray and Hinds

WITNESSES TO CORNER..... 7" W. Pine (S22 NBT), N 68° E, 48 Lks.



6" W. Pine, S21 NBT), N 48° W, 09 1/2 Lks.

5" W. Pine, (S28 NBT), S 43° W, 65 1/2 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was set from remains of 2 Original BT's, W. Pine 12", N 66° E, 16 Lks. down poor condition, but old blazes visible on pieces. W. Pine 16" S 65° W, 24 Lks., a stump with only traces of overgrowth remaining.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/8/1965  
REGISTERED LAND SURVEYOR