

✓  
MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 44/43 N.R. 15 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner for sections  $\frac{35}{36}$  T44N R15W  
2/1 T43N R15W

CORNER MONUMENT 1" Iron pipe with 4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED Frank J. Bray with M Burnis

WITNESSES TO CORNER..... 16" R. Pine (S1)(NBT) S32°E, 35½ Links



16" R. Pine (S2)(NBT) S 39° W, 62 Links

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

Placed on line and the single proportioned measurement between township corner to east and 1/4 corner 2½ miles to west. No original evidence found.

**SURVEYOR'S SEAL**

SIGNED Frank J. Bray DATE 10/16/67  
Frank J. Bray  
REGISTERED LAND SURVEYOR