

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. <u>43</u> N. R. <u>15</u> W.		<u>J-7, I-7</u>
2. PROPERTY CONTROLLING IN SECTION <u>23</u> T. <u>43</u> N. R. <u>15</u> W.		<u>1</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on November 1 & 3 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Woodposts:

I-7	W. Pine	20	N55°W	4	links
	W. Pine	6	S60°E	9	links
J-7	W. Pine	30	S35°E	38	links
	W. Pine	22	N05°W	34	links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-7 This corner was placed 75 links north of location of section corner which would be located in river. Section corner re-established by double proportioned measurement between section corners 1 mile to the north, east and south and 1/4 corner 1/4 mile west.

J-7 This corner was placed midway and on a line between section corners to the east and to the west. No original evidence found.

1. This corner was placed midway and on a line between the section corner to the west and 1/4 corner to the east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All 1" iron pipe with 1/2" aluminum cap.

I-7	10" W. Pine	(S15)(NBT)	N07°W	Magnetic	7.0'
	12" W. Pine	(S15)(NBT)	S77°W	Magnetic	15.1'
J-7	9" Hemlock	(1/8) (NBT)	N55°W	Magnetic	11.5'
	11" Hemlock	(1/8) (NBT)	N05°E	Magnetic	16.1'
1.	18" Hemlock	(W 1/16) (BT)	N88°W	Magnetic	8.2'
	11" Hemlock	(W 1/16) (BT)	N45°E	Magnetic	25.2'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Frank J. Bray CHIEF OF SURVEY PARTY DATE 2/9/73
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575