

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> <sup>N.</sup> <del>S.</del> , R. <u>15</u> <sup>E.</sup> <del>W.</del>	<u>1-6</u>
2. PROPERTY CONTROLLING IN SECTION <u>14</u>	, T. <u>43</u> <sup>N.</sup> <del>S.</del> , R. <u>15</u> <sup>E.</sup> <del>W.</del>	<u>3,10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> <del>S.</del> , R. _____ <sup>E.</sup> <del>W.</del>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on November 1 1972 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Woodpost:**

I-6	Beech	4	S30°E	14 links
	Beech	5	N45 W	20 links

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- I-6** This corner was placed midway and on a line between section corners to the north and to the south. No original evidence found.
- 10.** This corner was placed midway and on a line between the section corner to the south and  $\frac{1}{4}$  corner to the north.
- 3.** This corner was placed midway and on a line between the section corner to the north and  $\frac{1}{4}$  corner to the south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**All: 1" iron pipe with 4" aluminum cap. All bearings are magnetic.**

I-6	10" R. Maple	(1/8)	(NBT)	S87°W	4.4'
	21" Hemlock	(1/8)	(NBT)	S36°E	11.3'
3.	6" Spruce	(N 1/16)	(BT)	N59°E	27.8'
	14" W. Pine	(N 1/16)	(BT)	S56°E	45.0'
10.	6" R. Maple	(S 1/16)	(BT)	N64°E	9.9'
	7" R. Maple	(S 1/16)	(BT)	S59°W	20.8'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Frank J. Bray CHIEF OF SURVEY PARTY DATE 2/9/73  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575