LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -:	LOCATED IN-:	CORNER	R CODE NUMBER
1. PUBLIC LAND SURVEY	T _13K , R 1	5 W. G-h	
2. PROPERTY CONTROLL- ING IN SECTION	_ ,T 43 §, R1	5 w. 3.10	<u>o</u>
3. MISCELLANEOUS PROPERTY IN SECTION			
4. LOT NO, REC	ORDED PLAT		
5. PRIVATE CLAIMS			REGISTER OF DEEDS STAMP AND FILING NUMBER
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on November 8 & 10 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law: A. Description of original monument and accessories and/or subsequent restoration:			
Woodpost:		1	
G-4 Balsam	0 7 N32 E	4 links	
B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: G-4 This corner was placed midway and on a line between section corners to the north and to the south. No original evidence found. 3. This corner was placed midway and on: a line between the section corner to			
	corner to the		tion comes to the gouth and b comes
10. This corner was placed midway between section corner to the south and 4 corner to the north.			
C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: All 1" iron pipe with 4" aluminum cap. All bearings are magnetic.			
G-4 9" Beech (1/2 9" Hemlock (1/2	s) (NBT) N47 ⁰ s) (NBT) 845 ⁰	w 17.3'	
3. 6" H. Maple (N 1/16) (BT) NA N 1/16) (MT) NS	00E 10.1'	
10. 5" R. Pine ('5 E 27.7'	
	, , , ,		DATE
SURVEYOR'S MICHIGAN RE			
FOR STATE AND UNITED STATES AGENCIES:			
SIGNED BY	CHIEF OF SURVEY PARTY	,	DATE
APPROVED AND SIGNED BY	MICHIGAN REGIS	FRED LAND SURVEYED	DATE 2/9/33 (SEAL)
	Frank J. Bi	ray -	(SEAL)