

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>2</u> , R. <u>15</u> E. <u>W.</u>	<u>B-5</u>
2. PROPERTY CONTROLLING IN SECTION <u>18</u>	, T. <u>43</u> N. <u>2</u> , R. <u>15</u> E. <u>W.</u>	<u>1</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 10-17 19 73 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**B-5 Woodpost:**

Sugar	12	N40°W	9 links
Beech	6	S45°E	19 links

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- B-5 This corner was placed on line and the single proportioned measurement between section corners to the east and to the west.**
- 1 This corner was placed on a line and the single proportioned measurement between the section corner to the west and 1/4 corner to the east.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**All: 1" iron pipe with 1/2" aluminum cap. All: bearings are magnetic**

**B-5**  
 9" H. Maple (1/8) (NBT) N48°W 1.0'  
 11" H. Maple (1/8) (NBT) N83°E 2.3'

**1 7" Dead W. Pine (W 1/16) (BT) N75°W 75.6'**  
**No other trees near.**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Frank J. Bray CHIEF OF SURVEY PARTY DATE 10-24-73  
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575