

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> <sup>N.</sup> / <sub>S.</sub> , R. <u>15</u> <sup>E.</sup> / <sub>W.</sub>	<u>F-7</u>
2. PROPERTY CONTROLLING IN SECTION <u>21</u>	, T. <u>43</u> <sup>N.</sup> / <sub>S.</sub> , R. <u>15</u> <sup>E.</sup> / <sub>W.</sub>	<u>1.2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> / <sub>S.</sub> , R. _____ <sup>E.</sup> / <sub>W.</sub>	_____
4. LOT NO. _____	, RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 16 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**F-7 Woodpost:**

B. Ash 10 S82°E 60 links  
 B. Ash 12 N37°W 16 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**F-7 This corner was placed midway and on a line between the section corners to the east and to the west.**

**1 This corner was placed midway and on a line between the section corner to the west and  $\frac{1}{4}$  corner to the east.**

**2 This corner was placed midway and on a line between the section corner to the east and  $\frac{1}{4}$  corner to the west.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All: 1" iron pipe with $\frac{1}{4}$ " aluminum cap.		All: bearings are magnetic.	
F-7	10" Cedar (1/8) (NBT) N85°W	44.2'	
	7" Cedar (1/8) (NBT) N86°E	35.7'	
1	17" W. Pine (W 1/16 BT) N25°E	23.6'	
	14" R. Pine (W 1/16 BT) S36°E	11.0'	
2	7" J. Pine (E 1/16) (BT) N38°W	54.8'	
	10" J. Pine (E 1/16) (BT) S61°E	58.3'	

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Frank J. Bray CHIEF OF SURVEY PARTY DATE 10-25-73  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575