

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 43N R 15W	E8
	T 43N R 15W	G8
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on E8 03/04/2010
G8 02/07/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E8) Quarter corner common to Sections 20-21. 1961 - Remonumented by Billy D. Buckler RLS in the original position at record bearing and distance from Cedar BT N49E 17 links, in poor condition with overgrowth and scribe marks visible. Set 1" I.pipe with 4" brass cap. 8" Cedar N38E 46 links, 6" Tamarack S72E 47 links.

(G8) Quarter corner common to Sections 21 and 22. 1973 - Reestablished by F.J.Bray RLS midway and on line between Section corners to north and south. Set 1"ID I.pipe with 4" aluminum cap. 5" Cedar S88E 20.6', 7" W.Pine S27W 11.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E8) Found the 1961 monument in good condition and at record bearing and distance from the 1961 witnesses. The Cedar is in good condition. The Tamarack is dead. The original B.T. Cedar is not visible above the snowline (1 ft. deep). Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(G8) Found the 1973 monument in good condition and at record bearing and distance from the 1973 witnesses, both in good condition. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E8) Fd. 1"ID I.pipe with 4" brass cap.
Set measuring nail with MDNR tag in the side of:
12" Cedar N44E 30.7' mrkd "1/4S" 1961 NBT
8" B.Spruce S63E 35.4' mrkd "1/4S NBT"
12" B.Spruce S19E 50.75' do
10" B.Spruce S64W 44.6' do
Bearings are magnetic.

(G8) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail/tag in:
8" Cedar S83E 21.0' old blazes open 1973 NBT
11" W.Pine S34W 12.05' mrkd "1/4S" do
11" Hemlock N76W 11.3' mrkd "1/4S NBT"
6" Hemlock N12E 34.55' do
Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*
Surveyor's Michigan License No. 33986

Date 03/08/2011

For the Michigan Department of Natural Resources, Office of Land and Facilities

