

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 21 T 43N R 15W	F8
	S 21 T 43N R 15W	9
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Stephan J. Szyszkoski, in a field survey on F8 02/08/2011 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F8) Center of Section 21. Not established in the original survey.

(9-Sec. 21) East 1/16 corner, Section 21. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F8) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(9-Sec. 21) Established the corner midway and on a straight line between Quarter corner 1324.07' East and Center of Section 21 1324.07' West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 6" Cedar S19E 43.1' mrkd "CS BT"
 8" Cedar S39W 37.75' do
 12" Cedar N72E 26.65' do
 10" Maple N14E 14.55' do
 Bearings are magnetic.

(9) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 7" W.Pine N66E 23.4' mrkd "E1/16 BT"
 10" W.Pine North 33.25' do
 5" W.Pine S32W 14.0' do
 6" W.Pine N78W 32.7' do
 Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 03/08/2011

For the Michigan Department of Natural Resources, Office of Land and Facilities

